

Subregional RTEP Committee - Western DEOK Supplemental Projects

May 17, 2024

Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process



DEOK Transmission Zone M-3 Process Mitchell

Need Number: DEOK-2023-003

Process Stage: Solutions Meeting 05/17/2024

Previously Presented: Needs Meeting 04/21/2023




Project Driver: Customer Service

Specific Assumption Reference:

Duke Energy Ohio & Kentucky Local Planning Assumptions slide 5

Problem Statement:

Duke Energy Distribution has requested additional capacity delivery through Mitchell substation. There is only one 138/13 kV, 22MVA transformer which connects to all three distribution feeders. The transformer is expected to start exceeding nameplate in 2025.



Need Number: DEOK-2023-003

Process Stage: Solutions Meeting 05/17/2024

Previously Presented: Needs Meeting 04/21/2023

Project Driver: Customer Service

Specific Assumption Reference:

Duke Energy Ohio & Kentucky Local Planning Assumptions slide 5

Potential Solution:

Relocate 138/69 kV TB 4 to make room for a 2nd 22 MVA distribution transformer, TB 6. Install a circuit breaker on the high side of TB 4 to reconnect it to 138 kV Bus 4. Install a circuit switcher on the high side of TB 6 to connect it to 138 kV Bus 4. Rework distribution feeders transferring some load from the existing distribution transformer to TB 6.

Alternatives: none


Estimated Transmission Cost: \$1,870,984

Proposed In-Service Date: 12/26/2025

Project Status: Engineering

Model: 2023 RTEP

**Bubble Diagram Not Applicable
Station Modifications Only**



Need Number: DEOK-2023-006

Process Stage: Solutions Meeting 05/17/2024

Previously Presented: Needs Meeting 04/21/2023




Project Driver: Customer Service

Specific Assumption Reference:

Duke Energy Ohio & Kentucky Local Planning Assumptions slide 5

Problem Statement:

Merrel substation has two 69/13 kV, 10 MVA transformers that feed mostly industrial load. TB1 is loaded to 85% and TB2 has exceeded nameplate capacity several times in the last few summers. An industrial customer is expanding and has asked for an additional 5 MVA of service by the first quarter of 2027, with an expectation that 14 MVA may eventually be needed. The substation is land locked and lacks adequate safety clearances such that a complete substation outage is needed for maintenance. There are no options in the area to tie out customer load, or isolate substation equipment without the customer opening their switches.



Need Number: DEOK-2023-006

Process Stage: Solutions Meeting 05/17/2024

Previously Presented: Needs Meeting 04/21/2023

Project Driver: Customer Service

Specific Assumption Reference:

Duke Energy Ohio & Kentucky Local Planning Assumptions slide 5

Potential Solution:

Retire the existing substation. Expand the substation area to allow for new equipment installation meeting adequate safety clearances. Install new 69 kV bus, switch separated into two sections. Reconnect the 69 kV feeders to the bus with motorized switches and transmission line sectionalizing. Install two 69/13 kV, 22 MVA transformers, each connected to the 69 kV bus with circuit switchers. Install two new open air breaker sections of 13 kV bus to reconnect distribution feeders.

Alternatives: none


Estimated Transmission Cost: \$2.553M

Proposed In-Service Date: 04/23/2027

Project Status: Engineering

Model: 2023 RTEP

**Bubble Diagram Not Applicable
Station Modifications Only**





DEOK Transmission Zone M-3 Process Millville - Layhigh

Need Number: DEOK-2024-001

Process Stage: Solutions Meeting 05/17/2024

Previously Presented: Needs Meeting 01/19/2024

Project Driver: Equipment Condition, Performance and Risk

Specific Assumption Reference:

Duke Energy Ohio & Kentucky Local Planning Assumptions slides 7-8

Problem Statement:

A 69 kV feeder section that runs from Millville (Duke) to Layhigh (Butler Rural Electric Cooperative) is in deteriorating condition. Inspections have recorded 38 structure rejects due to ground line rot, pole top rot and bird holes. There are ten open ground lines. Since 2018 there have been 36 interruptions on the line, 14 sustained and 22 momentary, with an average of 274 minutes/outage and 96,000 CMI/outage. The outage causes vary, consisting of broken or damaged insulators, conductors, or crossarms, vegetation encroachment, lightning, and vehicle impacts. The entire feeder, end to end, serves 25,561 customers and connects Butler Rural Electric Cooperative substations: Colerain, Ross, Layhigh, Stillwell-Beckett, Oxford, and Reily.




Line Characteristics:

Original Install Date: 1955

Length: 3.23 miles / 83 poles

Construction Type: Single wood pole with suspension insulators

Conductor Type: 4/0-6/1 ACSR





DEOK Transmission Zone M-3 Process Millville - Layhigh

Need Number: DEOK-2024-001

Process Stage: Solutions Meeting 05/17/2024

Previously Presented: Needs Meeting 01/19/2024

Project Driver: Equipment Condition, Performance and Risk

Specific Assumption Reference:

Duke Energy Ohio & Kentucky Local Planning Assumptions slides 7-8

Potential Solution:

From Layhigh to the tap to Millville; replace wooden structures with steel pole structures, reconductor the line with 954ACSR, retire a switch between Layhigh and the tap. The new ratings increase to 150/150/174 MVA summer, 189/189/206 MVA winter.


Alternatives: none

Estimated Transmission Cost: \$8.496M

Proposed In-Service Date: 04/02/2026

Project Status: Engineering

Model: 2023 RTEP



Appendix

High Level M-3 Meeting Schedule

Assumptions	Activity	Timing
	Posting of TO Assumptions Meeting information	20 days before Assumptions Meeting
	Stakeholder comments	10 days after Assumptions Meeting
Needs	Activity	Timing
	TOs and Stakeholders Post Needs Meeting slides	10 days before Needs Meeting
	Stakeholder comments	10 days after Needs Meeting
Solutions	Activity	Timing
	TOs and Stakeholders Post Solutions Meeting slides	10 days before Solutions Meeting
	Stakeholder comments	10 days after Solutions Meeting
Submission of Supplemental Projects & Local Plan	Activity	Timing
	Do No Harm (DNH) analysis for selected solution	Prior to posting selected solution
	Post selected solution(s)	Following completion of DNH analysis
	Stakeholder comments	10 days prior to Local Plan Submission for integration into RTEP
	Local Plan submitted to PJM for integration into RTEP	Following review and consideration of comments received after posting of selected solutions

Revision History

5/7/2024 – V1 – Original version posted to pjm.com