

# Sub Regional RTEP Committee: Western DEOK Supplemental Projects

April 22, 2022

# Needs

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process



# DEOK Transmission Zone M-3 Process Willey

**Need Number:** DEOK-2022-005

**Process Stage:** Needs Meeting 04-22-2022




**Project Driver:** Customer Service

**Specific Assumption Reference:**

Duke Energy Ohio & Kentucky Local Planning Assumptions slide 9

**Problem Statement:**

Duke Energy Distribution has asked for a second delivery point at Willey substation. The single 138/34 kV, 56 MVA distribution transformer at Willey is peaking at 100% of rated capacity.



# Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process

**Need Number:** DEOK-2021-012

**Process Stage:** Solutions Meeting 04-22-2022

**Previously Presented:** Needs Meeting 11-19-2021




**Project Driver:** Customer Service

**Specific Assumption Reference:**

Duke Energy Ohio & Kentucky Local Planning Assumptions slide 9

**Problem Statement:**

Duke Energy Distribution has requested a new delivery point near Kennel Road in Butler County Ohio. An existing customer is relocating to a new site for expansion. 10 MVA is required by Q1 2024 with a total 16 MVA required by Q1 2025.





# DEOK Transmission Zone M-3 Process Kennel

**Need Number:** DEOK-2021-012

**Process Stage:** Solutions Meeting 04-22-2022

**Previously Presented:** Needs Meeting 11-19-2021

**Project Driver:** Customer Service

**Specific Assumption Reference:**

Duke Energy Ohio & Kentucky Local Planning Assumptions slide 9

**Proposed Solution:**

Construct a new 69 kV ring bus substation named Kennel. Install six circuit breakers and one 69/13 kV, 22 MVA transformer. Loop the 69 kV feeders currently feeding adjacent Miller substation through Kennel. Refeed Miller from Kennel. Distribution will feed the relocating customer from this new substation.

**Ancillary Benefits:** Operational flexibility, Infrastructure resilience




**Alternatives:** none

**Estimated Transmission Cost:** \$6,671,179

**Proposed In-Service Date:** 12-31-2023

**Project Status:** Scoping

**Model:** 2021 RTEP



# Appendix

# High Level M-3 Meeting Schedule

Assumptions	Activity	Timing
	Posting of TO Assumptions Meeting information	20 days before Assumptions Meeting
	Stakeholder comments	10 days after Assumptions Meeting
Needs	Activity	Timing
	TOs and Stakeholders Post Needs Meeting slides	10 days before Needs Meeting
	Stakeholder comments	10 days after Needs Meeting
Solutions	Activity	Timing
	TOs and Stakeholders Post Solutions Meeting slides	10 days before Solutions Meeting
	Stakeholder comments	10 days after Solutions Meeting
Submission of Supplemental Projects & Local Plan	Activity	Timing
	Do No Harm (DNH) analysis for selected solution	Prior to posting selected solution
	Post selected solution(s)	Following completion of DNH analysis
	Stakeholder comments	10 days prior to Local Plan Submission for integration into RTEP
	Local Plan submitted to PJM for integration into RTEP	Following review and consideration of comments received after posting of selected solutions



# Revision History

4/12/2022 – V1 – Original version posted to pjm.com