## **Dominion Supplemental Projects**

Transmission Expansion Advisory Committee August 31, 2021



### Needs

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process



# Dominion Transmission Zone: Supplemental Equipment Material Condition, Performance and Risk

Need Number: DOM-2021-0044

**Process Stage:** Need Meeting 08/31/2021

**Project Driver:** Equipment Material Condition, Performance and Risk


### **Specific Assumption References:**

See details on Equipment Material Condition, Performance and Risk in Dominion's Planning Assumptions presented in December 2020.

#### **Problem Statement:**

Clifton Forge TX#2 is a 250 MVA, 230/138/13.2 kV three-phase auto transformer bank that was manufactured in 1996. This transformer bank has been identified for replacement based on the results of Dominion's transformer health assessment (THA) process. Detailed drivers include:

- Age (approaching 30 years old).
- Reduced BIL ratings (2 levels below standard).
- Degraded porcelain type bushings.
- Oil DGA shows elevated levels of CO and CO2 indicating potential degradation of dielectric paper insulation.
- Mechanical design issue was observed with conservator tank mounting (tank began to collapse and start pulling away from the tank anchor points).
- THA score less than 80.





Dominion Transmission Zone: Supplemental Equipment Material Condition, Performance and Risk

Need Number: DOM-2021-0060

Process Stage: Need Meeting 08/31/2021

Project Drivers: 1) Operational Flexibility and Efficiency

2) Customer Service


### **Specific Assumption References:**

See details on Operational Flexibility and Customer Service in Dominion's Planning Assumptions presented in December 2020.

#### **Problem Statement:**

Dominion Energy has identified a need to retire Roanoke Valley NUG 230kV Substation and to remove the terminations of the double circuit Lines #2012 and #2060.

- No load is served from Roanoke Valley NUG 230kV Substation post retirement of the generator. The assets are no longer required, will need continuous maintenance to avoid risk to reliability.
- DEV Distribution has a customer locating on the property.





### Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process



## Dominion Transmission Zone: Supplemental Do No Harm Analysis

Need Number: DOM-2021-0032 DNH

**Process Stage:** Solutions Meeting 08/31/2021

**Project Driver:** Do No Harm Analysis


### **Specific Assumption References:**

Customer load request will be evaluated per Dominion's Facility Interconnection Requirements Document and Dominion's Transmission Planning Criteria.

### **Problem Statement:**

PJM has identified a 300MW N-1-1 Load Drop violation for the loss of Line #2081 (Paragon Park to Sterling Park) and Line #2033 (Davis Drive to Reston) during the 2021 Do-No-Harm analysis.

The violation was caused by Supplemental Project DOM-2021-0032 in the Dominion Zone.





## Dominion Transmission Zone: Supplemental Do No Harm Analysis

Need Number: DOM-2021-0032 DNH

**Process Stage:** Solutions Meeting 08/31/2021

**Proposed Solution:** 

Cut and Loop Line 2079 (Sterling Park - Dranesville) into Davis Drive substation and install

two GIS 230kV breakers.

#### **Alternatives Considered:**

No feasible alternatives

**Estimated Cost:** \$15.0M


Transmission Line: \$5M

Substation: \$10M

**Projected In-service Date:** 06/15/2026

**Project Status:** Engineering

Model: 2025 RTEP





## Appendix



## High level M-3 Meeting Schedule

| Assumptions              | Activity  | Timing  |
|--------------------------|---|---|
|                          | Posting of TO Assumptions Meeting information         | 20 days before Assumptions Meeting  |
|                          | Stakeholder comments                                  | 10 days after Assumptions Meeting   |
|                          |   |   |
| Needs                    | Activity  | Timing  |
|                          | TOs and Stakeholders Post Needs Meeting slides        | 10 days before Needs Meeting  |
|                          | Stakeholder comments                                  | 10 days after Needs Meeting   |
|                          |   |   |
| Solutions                | Activity  | Timing  |
|                          | TOs and Stakeholders Post Solutions Meeting slides    | 10 days before Solutions Meeting  |
|                          | Stakeholder comments                                  | 10 days after Solutions Meeting   |
|                          |   |   |
| Submission of            | Activity  | Timing  |
| Supplemental             | Do No Harm (DNH) analysis for selected solution       | Prior to posting selected solution  |
| Projects & Local<br>Plan | Post selected solution(s)                             | Following completion of DNH analysis  |
|                          | Stakeholder comments                                  | 10 days prior to Local Plan Submission for integration into RTEP                            |
|                          | Local Plan submitted to PJM for integration into RTEP | Following review and consideration of comments received after posting of selected solutions |



### **Revision History**

08/20/2021 – V1 – Original version posted to pjm.com.

