

TEAC Committee ComEd Supplemental Projects

Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process



ComEd Transmission Zone M-3 Process McCook Transformers

Need Number: ComEd-2021-005

Process Stage: Solution Meeting November 2, 2021 **Previously Presented:** Need Meeting October 5, 2021

Project Driver:

Operational Flexibility and Efficiency

Equipment Material Condition, Performance and Risk

Customer Service

Specific Assumption References:


Enhancing system functionality, flexibility, visibility, or operability

• Transmission infrastructure replacements (EOL/condition/obsolescence) that are consistent with efficient asset management decisions

Building to support future economic growth

Problem Statement:

- The two existing autotransformers at McCook are among the most heavily loaded on the ComEd system and have been loaded above the load cycling threshold 28 times in the last 6 years which reduces the overall life expectancy of these units
- TR 84 autotransformer is 55 years old with insulation at end of expected design life. The transformer internal blocking was found loose and retightened in 2005. After reblocking, the transformer is only capable of achieving pressures of 60% of original factory requirements.
- Data Center loading has increased in the area in recent years and is expected to continue.





ComEd Transmission Zone M-3 Process McCook Transformers

Need Number: ComEd-2021-005

Process Stage: Solutions Meeting November 2, 2021

Proposed Solution:

Install 2 new autotransformers

Replace reblocked TR 84

Reconductor 2 miles out of 2.5 miles on 138 kV McCook

- Ridgeland to obtain a minimum rating of 351/449/459/498 MVA (SN/SLTE/SSTE/SLD)

Estimated transmission cost: \$36M

Alternatives Considered:

Do Nothing


Load cycling on transformers still an issue

Increased risk from aging equipment

Projected In-Service: 12/31/25

Project Status: Conceptual

Model: 2026 RTEP



Appendix

High Level M-3 Meeting Schedule

| Assu | mı | pti | on | S |
|------|----|-----|-------|---|
| | | | • • • | _ |

| Activity | Timing |
|---|------------------------------------|
| Posting of TO Assumptions Meeting information | 20 days before Assumptions Meeting |
| Stakeholder comments | 10 days after Assumptions Meeting |

Needs

| Activity | Timing |
|--|------------------------------|
| TOs and Stakeholders Post Needs Meeting slides | 10 days before Needs Meeting |
| Stakeholder comments | 10 days after Needs Meeting |

Solutions

| Activity | Timing |
|--|----------------------------------|
| TOs and Stakeholders Post Solutions Meeting slides | 10 days before Solutions Meeting |
| Stakeholder comments | 10 days after Solutions Meeting |

Submission of Supplemental Projects & Local Plan

| Activity | Timing |
|---|---|
| Do No Harm (DNH) analysis for selected solution | Prior to posting selected solution |
| Post selected solution(s) | Following completion of DNH analysis |
| Stakeholder comments | 10 days prior to Local Plan Submission for integration into RTEP |
| Local Plan submitted to PJM for integration into RTEP | Following review and consideration of comments received after posting of selected solutions |

Revision History

10/22/2021 – V1 – Original version posted to pjm.com